

PROJECT PROFILE - ROW HOME DEMOLITION

Chester, PA

Date: Sept. 2010 - January 2011



Demolition clears the way for a new development.



Objective:

Demolish 214 Row Homes and install new infrastructure for a new townhome development on the I95 corridor near the Commodore Barry Bridge.

Solution:

SCE was contracted to demolish the Row Homes and install new infrastructure on an extremely fast track. Crews worked 14 hours per day, 6 days per week to accomplish this monumental task. An average of 3 homes per day were prepped and demolished and their footers were removed and backfilled. All masonry materials were crushed on site for reuse during development. In addition, over 36,400 cubic yards of debris were processed and loaded for off-site disposal.

SCE installed sanitary sewer, water, gas and storm sewer infrastructure for the project in sequence with the demolition effort. SCE also installed the underground stormwater collection system.

The project was completed on time and with over 9,300 accident and injury free hours.

SERVICES PROVIDED

- Demolition
- Infrastructure Installation
- Site Work

